



LOCATION PLAN

# DEMOLITION NOTES

ACCESS FOR VEHICLES/TRUCKING OF DEBRIS SHALL BE THROUGH 44 CHURCH STREET REAR PARKING LOT. REMOVE WALLS, PARTITIONS, MECHANICAL AND ELECTRICAL SERVICES, AND ASSOCIATED ITEMS AS NOTED. DISCONNECT ALL POWER AND ILLUMINATION AS NECESSARY FOR THE COMPLETION OF REMOVAL OPERATIONS. DISCONNECT /CAP ALL PLUMBING SERVICE PIPING NECESSARY FOR THE COMPLETION OF REMOVAL OPERATIONS. CAP AND ABANDON SERVICE LINES NOT TO BE EXTENDED OR REUSED.

REROUTE SERVICES WHICH MUST BE MAINTAINED. REFER TO PLUMBING & ELECTRICAL DRAWINGS FOR DETAILS. ALL REMOVED EQUIPMENT ITEMS, WALLS, MECHANICAL, ELECTRICAL, AND FINISH MATERIALS OTHER THAN 'OWNER SALVAGED' ITEMS SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE CAREFULLY & APPROPRIATELY REMOVED FROM THE SITE AND DISCARDED IN ACCORDANCE WITH GOVERNMENT REQUIREMENTS.

EXISTING UTILITIES AND SERVICE LINES DISCOVERED DURING REMOVAL OPERATIONS SHALL BE IMMEDIATELY REPORTED. PROVIDE SUITABLE PROTECTION FOR ADJACENT EXISTING AREAS BEFORE, DURING AND FOLLOWING REMOVAL & DEMOLITION OPERATIONS. DEBRIS SHALL BE CAREFULLY REMOVED USING ADEQUATELY ENCLOSED CONTAINERS TO PREVENT UNWANTED DEBRIS SPILL DURING REMOVAL.

NO MATERIAL SHALL BE BURNED, STORED OR SOLD IN EITHER THE BUILDING OR ON THE SITE. ALL REMOVED MATERIAL AND DEBRIS, UNLESS IDENTIFIED OTHERWISE, SHALL BECOME THE CONTRACTOR'S PROPERTY AND SHALL BE REMOVED IMMEDIATELY AND COMPLETELY FROM THE BUILDING AND THE SITE. LEAVE THE SITE CLEAN, READY FOR FURTHER CONSTRUCTION.

DEMOLITION  
ALL WALLS AND CEILING  
OUTSIDE OF THE COLORED ZONES

DEMO FLOOR PLAN

1/4" = 1'