



SCOPE OF WORKS

**Exterior Painting & Roof
4 Cedar Park Road
Devonshire
Site #: 4024000**

Please provide a quotation for labor to make the below repairs. BHC will supply all paint, bleach and bond contractor is expected to supply all tools and sundries.

1. **WALLS:** - Cost labour buildings and storage rooms
 - a. Prepare walls thoroughly, repairing all cracks, by approved methods, to receive three (3) coats of paint as per Manufacturer's specifications. All exposed and bare concrete/stone surfaces must receive one (1) coat primer sealer prior to paint application as per Manufacturer's specifications.
 - b. Apply one (1) tinted primer and one (2) coats of finish paint as per Manufacturer's specifications. Color is to be Newport Blue satin (same) as supplied by Pembroke Paint.

2. **WOODWORK, RAFTER FEET, BOUNDARY WALLS & TRIM:** - Cost labour
 - a. Clean, prepare by approved method, to receive two (2) coats of paint as per Manufacturer's specifications. All exposed and bare wood surfaces must receive one (1) coat primer undercoat prior to paint application as per Manufacturer's specifications.
 - b. Apply two (2) coats of finish paint as per Manufacturer's specifications. Woodworks and trim are to Gloss White and/or Bermuda Green to match existing.
 - c. Boundary and property walls outbuildings, pump rooms are to match the house color, with white trim if any.

3. **PORCHES & WALKWAYS:** – Cost labour:
 - a. Pressure Wash – and clean porch cement areas and walkways. Porch floors are to receive two coats of grey non-skid porch paint.

4. **ROOF** – To supply all labour: - **BHC to supply paint**
 - a. Pressure Wash/Clean with bleach - clean roof to receive crack sealant/paint as per Manufactures specifications.
 - b. To make all repairs as needed to the roof area of building prior to painting.
 - c. Apply two (2) coats of SKB paint/sealer, white in color, and must be compatible with existing roof finish.

**SPECIAL CARE AND ATTENTION TO BE GIVEN TO COVER ALL
HEDING AND TENANTS BELONGINGS AS NEEDED.
TO CLEAN, TIDY AND REMOVE ALL DEBRIS FROM SITE.**

